VVTA RFP 2021-17 DESIGN BUILD HESPERIA TRANSFER HUB ADDENDUM NO. 2

February 8, 2024

This addendum is provided to all known prospective proposers for clarification of the subject Request for Proposal (RFP).

The following questions were posed prior to the deadline for questions on 01/26/2024, along with the answers from VVTA staff:

- Q1: "Please confirm that we do not need to complete the Subcontractor listing as part of this RFP. Since we do not have a design yet, we don't have a way for the subcontractors to bid on the project. This is usually done after the design is completed through a competitive bidding process."
- A1: Per the state of CA DIR the PWC100 is to be completed by the awarding agency at the time of award. In order to be able to report the Prime and Subs for the project, DIR registration has to be confirmed by the Agency prior to award. So, we do require the subcontractor form to be completed if it is your intention to use subs on your project.
- Q2: "Please advise if Form P will be revised to exclude line item pricing per division. Since we do not have a design yet, we do not have a way for subcontractors to bid on the project, and therefore cannot provide an accurate breakdown of pricing per division."
- A2: Please see Addendum no. 1 for the corrected form.
- Q3: "Please advise if the pricing Form P can be revised? Since the RFP is not asking the teams to provide a complete design, we are not able to complete a detailed price proposal. We suggest the following items be included in the price proposal:
 "Design Fees
 "General Conditions Fees
 "Overhead & Profit Percentage
 "Allowance
 "Estimated Construction Cost"
- A3: Please see the updated form on Addendum No. 1.
- Q4: "Please advise if a Bid Bond is necessary for this project. Bid Bonds are usually provided during bidding on a fully designed project that is going to start construction right after the bid. Surety Companies require total square footage, building materials, and other information that we don't have yet because the project is not designed. We suggest removing this requirement and asking for a Letter of Bondability from the Bidder's Surety Company stating that they can bond for the total project budget. Then Payment and Performance bonds will be provided once construction starts."
- A4: Because of the Federal and State rules regarding the 2-step process, we are required to request a Bid Bond for the cost of the project prior to the opening of the proposals.

VVTA RFP 2021-17 DESIGN BUILD HESPERIA TRANSFER HUB ADDENDUM NO. 2

- Q5: "Regarding Question/ Answer 15, we respectfully request that VVTA revisit their response. The question asked about naming all subcontractors (to include construction subcontractors) at the time of the RFP submission. Naming all subcontractors at the RFP stage might be premature, as in a D/B project not all subcontractors have been finalized due to the evolving nature of the design after award. The answer appears to address subcontractor local preference. Would VVTA waive the requirement to name all subcontractors greater than one-half of one percent?"
- A5: The DIR has made it clear that we have to confirm the DIR registration of all primes and subcontractors on the project prior to award. We respectfully request that your provide your Subcontractor information with your proposal.
- Q6: "Regarding Question/ Answer 16, to ensure complete clarity, please confirm that while VVTA's DBE goal is 4.75%, bidders are NOT held to a DBE goal for this project?"
- A6: VVTA's Race Neutral goal is 4.75%. The IS NOT a contract goal on this project.
- Q7: "Question/ Answer 45 states that VVTA has no plans for EV infrastructure. However, per California Green Building Code section "5.106.5.3.1 EV Capable Spaces", Table 5.106.5.3.1, this project is required to provide a certain number of EV charging stations based on the overall parking count. We respectfully request that VVTA revisit their response to Question 45."
- A7: The project must comply with applicable Building Codes including EV ready/capable parking spaces. However, VVTA does not plan to have any bus charging infrastructure such as inductive or pantograph charging in the bus area.
- Q8: "Please provide the geotechnical report from the main facility construction project? This was not included in the as-builts provided in amendment 1."
- A8: The Geotechnical Report from 2008 for the construction of the VVTA Administration is attached as Exhibit 1 to the Addendum.
- Q9: "Can you provide a copy of the as builts of the existing VVTA Building at 17150 Smoke Tree St, Hesperia, CA 92345 so we can match finishes, construction type, and see where utility connections are coming from? The building, landscape, civil and structural plans will be very helpful to have. (If we can get this earlier than Feb 1st, when the addendum will be released, it will be very beneficial)
- A9: A link to the As-Build was included in Addendum No. 1 and is included below.
- Q10: "Can you provide a list of your utility providers at the current VVTA facility? Who is providing power, water, sewer, trash, etc?"
- A10: So Cal Edison, Southwest Gas, Advance Disposal, City of Hesperia Water for water and sewer.

VVTA RFP 2021-17 DESIGN BUILD HESPERIA TRANSFER HUB ADDENDUM NO. 2

- Q11: "Will you release the NEMA report?"
- A11: VVTA is unaware of a NEMA report.
- Q12: "Can you release a copy of the title report with plotted easements to determine if there are any utility easements?"
- A12: There is an easement on a parcel to the north of the 10-acre parcel, but not within the boundaries of the 10-acre parcel.
- Q13: "The RFP states that the contract period will be for 18 months, is this just for construction? Do you have an expected timeline for the design, construction plans and permitting process?"
- A13: VVTA anticipates that the project with be start to finish in 18 months.
- Q14: "The RFP states that "all costs of work" should be included but does this exclude costs for plan check applications fess, permit costs, utility connection fees and developer fees as these are all extreme unknowns that will be hard to calculate without submitting plans to the city for review? We can provide a budget but not exact costs. If you want a budget, can we include a separate line item in Form P, Price Proposal?"
- A14: These costs will be factored into the contingency with the awarded contractor.

Also included with this Addendum:

Exhibit 1 – Geotechnical report for the VVTA Hesperia Administration and Maintenance Facility.

As-Builts can be accessed via this link:

https://www.dropbox.com/scl/fo/r8qz8c0xbfspzcboftkbe/h?rlkey=jv5te2gm9fg4jkib0aq0y05 v8&dl=0

As stated in the RFP, all addenda must be acknowledged. Please use Attachment E included in the RFP package to acknowledge receipt of this addendum. Failure to acknowledge any addenda to this RFP may be a cause to deem Potential Proposer as "non-responsive."



DIAZ • YOURMAN

& ASSOCIATES

Geotechnical Services

A Report Prepared for:

Maintenance Design Group 1600 Stout Street, Suite 940 Denver, CO 80202

ADDENDUM REPORT NO. 1 PRELIMINARY GEOTECHNICAL INVESTIGATION VICTOR VALLEY TRANSIT AUTHORITY TRANSIT ADMINSTRATION, OPERATIONS, AND MAINTENANCE FACILITY HESPERIA, CALIFORNIA

Project No. 2006-059.02

by

Somadevan Niranjanan Civil Engineer 67023

V.R. Nadeswaran Geotechnical Engineer 2390

DiazeYourman & Associates 1616 East 17th Street Santa Ana, CA 92705-8509 (714) 245-2920

May 12, 2008





TABLE OF CONTENTS

| 1.0 | INTRODUCTION | 1 |
|------|--|---|
| 2.0 | FIELD INVESTIGATION, AND LABORATORY TESTING | 4 |
| 3.0 | SUBSURFACE CONDITIONS | 5 |
| 4.0 | PAVEMENT THICKNESS DESIGN | 6 |
| 5.0 | PLAN REVIEW, CONSTRUCTION OBSERVATION, AND TESTING | 7 |
| 6.0 | LIMITATIONS | 8 |
| 7.0 | BIBLIOGRAPHY | 9 |
| | | |
| APPE | NDIX A - LABORATORY TESTING A- | 1 |

LIST OF FIGURES

| Figure 1 - VICINITY MAP | 1 |
|-------------------------------|---|
| Figure 2 - SITE PLAN | 2 |
| Figure 3 - PAVEMENT THICKNESS | 6 |

1.0 INTRODUCTION


This report presents the results of the additional geotechnical investigation performed by Diaz•Yourman & Associates (DYA) for the proposed Victor Valley Transit Authority (VVTA) Transit Administration, Operations, and Maintenance Facility (Transit Facility) in Hesperia, California. Maintenance Design Group (MDG) authorized this additional work by email on April 28, 2008.

The proposed VVTA Transit Facility is located at the northeast quadrant of the intersection of Smoke Tree Street and E Avenue in Hesperia, California, as shown on the Vicinity Map, Figure 1. The approximate layout of the proposed project is shown on the Site Plan, Figure 2.

DYA previously performed a preliminary geotechnical investigation and provided preliminary recommendations in a report dated January 30, 2007 (DYA, 2007). The previous DYA report included preliminary recommendations for pavement thickness within the project site. Subsequently, in April 2008, pavement thickness recommendations were requested for E Avenue, west of the project site. A Traffic Index (TI) of 10 was provided by the design team.




Figure 1 - VICINITY MAP



Reference: Electronic Base Map Provided by Maintenance Design Group (2007)

Figure 2 - SITE PLAN



APPROXIMATE DYA BORING LOCATION(2007)

K:\datafls\PROJECTS\2006\2006-059.02\CADD/SITE PLAN Add No.dwg

The purpose of DYA's additional investigation was to provide pavement thickness design for E Avenue for a TI of 10. The scope of our services consisted of the following tasks:

- Collecting two bulk samples from E Avenue from the pavement subgrade.
- Performing laboratory tests on selected samples.
- Performing engineering analyses to develop asphalt concrete (AC) pavement thickness design.
- Preparing this addendum report to summarize our findings.

2.0 FIELD INVESTIGATION, AND LABORATORY TESTING

The field investigation, conducted on May 1, 2008, consisted of collecting bulk samples of the nearsurface materials at the locations shown on Figure 2. The sampling locations were chosen to provide areal coverage of the project site. Prior to performing the sampling, the locations were marked in the field and underground service alert (USA) was notified. The bulk samples were collected using a backhoe and sampling was performed to approximate depth of 4 feet.

Soil samples collected from the borings were re-examined in the laboratory to substantiate field classifications. Selected soil samples were tested for moisture content, sieve analyses, and pavement-supporting capacity (California R-Value). Laboratory test data are summarized on individual test reports in Appendix A.



3.0 SUBSURFACE CONDITIONS


The subsurface soils encountered in the samples from E Avenue mostly consisted of medium dense to dense silty sands. One R-value test performed on a sample showed an R-value of 67.



4.0 PAVEMENT THICKNESS DESIGN

Recommended minimum AC pavement sections are presented on Figure 3. The recommended minimum pavement sections were based on the following:

- California R-value of 50 for E Avenue.
- Caltrans design method.
- TI of 10, provided by the design team.



Compacted in-place natural soil or fill; the minimum is 95 percent relative compaction¹.

Figure 3 - PAVEMENT THICKNESS

For site preparation recommendations, see previous investigation report (DYA, 2007).

¹ Relative compaction refers to the in-place dry density of soil expressed as a percentage of the maximum dry density of the same material, as determined by the American Society for Testing Materials (ASTM) D1557-91 test method. Optimum moisture content is the moisture content corresponding to the maximum dry density, as determined by the ASTM D1557-91 test method.



5.0 PLAN REVIEW, CONSTRUCTION OBSERVATION, AND TESTING

DYA should be retained to review the final design, finished grading earthwork and plans and specifications for conformance with the intent of our recommendations. The review will enable DYA to modify the recommendations if final design conditions are different than presently understood.

During construction, DYA should provide field observation and testing to check that the site preparation, excavation, and finished grading conform to the intent of these recommendations, project plans, and specifications. This would allow DYA to develop supplemental recommendations as appropriate for the actual soil conditions encountered and the specific construction techniques used by the contractor.

As needed during construction, DYA should be retained to consult on geotechnical questions, construction problems, and unanticipated site conditions.



6.0 LIMITATIONS

This report has been prepared for this project in accordance with generally accepted geotechnical engineering practices common to the local area. No other warranty, expressed or implied, is made.

The analyses and recommendations contained in this report are based on the literature review, field investigation, and laboratory testing conducted in the area. The results of the field investigation indicate subsurface conditions only at the specific locations and times, and only to the depths penetrated. They do not necessarily reflect strata variations that may exist between such locations. Although subsurface conditions have been explored as part of the investigation, we have not conducted chemical laboratory testing on samples obtained or evaluated the site with respect to the presence or potential presence of contaminated soil or groundwater conditions.

The validity of our recommendations is based in part on assumptions about the stratigraphy. Observations during construction can help confirm such assumptions. If subsurface conditions different from those described are noted during construction, recommendations in this report must be re-evaluated. DYA should be retained to observe earthwork construction in order to help confirm that our assumptions and recommendations are valid or to modify them accordingly. In accordance with UBC Appendix Chapter 33 Section 3317, DYA cannot assume responsibility or liability for the adequacy of recommendations if we do not observe construction.

This report is intended for use only for the project described. In the event that any changes in the nature, design, or location of the facilities are planned, the conclusions and recommendations contained in this report should not be considered valid unless the changes are reviewed and conclusions of this report modified or verified in writing by DYA. We are not responsible for any claims, damages, or liability associated with the interpretation of subsurface data or reuse of the subsurface data or engineering analyses without our express written authorization.



7.0 **BIBLIOGRAPHY**

American Society for Testing and Materials (ASTM), 2005, Annual Book of Standards, Vols. 4.08 and 4.09, Soil and Rock.

Building News, 2007, "Greenbook," Standard Specifications for Public Works Construction.

California Department of Transportation, 2006, Highway Design Manual, Sixth Edition.

California Department of Transportation, 2006, Standard Specifications.

Diaz•Yourman & Associates, 2007, Preliminary Geotechnical Investigation, Victor Valley Transit Authority, Transit Administration, Operations, and Maintenance Facility, Hesperia, California, January 30, 2007.



APPENDIX A LABORATORY TESTING



APPENDIX A - LABORATORY TESTING

Diaz•Yourman & Associates (DYA) selected soil samples to be tested and the tests to be performed on the selected samples. Laboratory testing was performed by AP Engineering & Testing, Inc. Laboratory data are presented on Plates A1 through A3. We have reviewed and concur with the test results and accept full responsibility for their use in our analysis. A summary of the geotechnical laboratory testing is presented in Table A1.

| TEST NAME | PROCEDURE | PURPOSE | LOCATION | | | |
|---|--------------------------|----------------------------------|----------|--|--|--|
| Moisture Content | ASTM D2216-92 | Classification, index properties | Plate A1 | | | |
| Grain-Size Distribution | ASTM D422-63 | Classification, index properties | Plate A2 | | | |
| Resistance (R-) Value | ASTM D2844-69 CTM 301 | Pavement thickness design | Plate A3 | | | |
| Notes: • ASTM = American Society for Testing and Materials • CTM = Caltrans Test Method | | | | | | |

Table A1 - LABORATORY TESTING SUMMARY



AP Engineering & Testing, Inc.


MOISTURE AND DENSITY TEST RESULTS

Client:Diaz YourmanProject Name:VVTA PavementProject Location:2006-059.02

AP No.: 28-0503 Date: 05/01/08

| Boring No. | Sample No. | Sample Depth (ft) | Moisture Content (%) | Dry Density (pcf) |
|---------------|---------------|----------------------|-------------------------|----------------------|
| EP-2 | - | - | 2.43 | NA |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |

Tel. (909) 869-6316, Fax (909) 869-6318



* NA = Not Available

| | Project Name: | VVTA Pavement | |
|-------------------------------|---------------|---------------|-------------|
| GRAIN SIZE DISTRIBUTION CURVE | Project No.: | 2006-059.02 | |
| | Date: | 5/1/2008 | |
| ASTM D 422 | AP No: | 28-0503 | PLATE A2 |




AP Engineering & Testing, Inc.

R-VALUE TEST DATA

ASTM D2844


| Project Name: Project Number: | VVTA Pavement | | Tested By: Checked By: | | | 05/01/08 |
|----------------------------------|--------------------|--------------|---------------------------|-------|-------|----------|
| Boring No.: | EP-2 | | | 7.0 | Duto. | |
| • | Bulk | Depth (ft.): | NA | | | |
| Location: | - | , | | | | |
| Soil Description: | Sand w/silt | | - | | | |
| Mold Number | | E | F | D | | |
| Water Added, g | | 61 | 66 | 64 | | |
| Compact Moistur | e(%) | 8.7 | 9.2 | 9.0 | | |
| Compaction Gage | e Pressure, psi | 250 | 220 | 230 | | |
| Exudation Pressu | ıre, psi | 660 | 102 | 430 | | |
| Sample Height, Ir | nches | 2.5 | 2.5 | 2.5 | | |
| Gross Weight Mold, g | | 3099 | 2986 | 3115 | | |
| Tare Weight Molo | 1, g | 1957 | 1871 | 1971 | | |
| Net Sample Weig | ıht, g | 1142 | 1115 | 1144 | | |
| Expansion, inche | sx10 ⁻⁴ | 0 | 0 | 0 | | |
| Stability 2,000 (16 | 60 psi) | 18/32 | 26/46 | 21/36 | | |
| Turns Displaceme | ent | 3.96 | 3.71 | 3.85 | | |
| R-Value Uncorrec | cted | 72 | 63 | 69 | | |
| R-Value Correcte | d | 72 | 63 | 69 | | |
| Dry Density, pcf | | 127.3 | 123.7 | 127.2 | | |
| Traffic Index | | 8.0 | 8.0 | 8.0 | | |
| G.E. by Stability | | 0.48 | 0.63 | 0.52 | | |
| G.E. by Expansio | n | 0.00 | 0.00 | 0.00 | | |



 $G_{f} = 1.5$

Remarks:

0.0 % Retained on the 3/4"



DISTRIBUTION

5 copies: Mr. John Wulfmeyer Maintenance Design Group 3920 Stansbury Avenue Sherman Oaks, CA 91423

QUALITY CONTROL REVIEWER

Saroj Weeraratne, Ph.D, P.E., G.E. Senior Engineer

SN/VRN:cfp

